



DETAIL WATERPROOFING




BUILD UP REMOVAL TO PERIMETER TO ALLOW VENTING BEHIND UPSTAND ANGLE




REMOVE WORKS AT CENTRED LOCATIONS
AJACENT TO UPSTAND

MAIN AREA WATERPROOFING



NOTES


- 1 SEAL FLASHING USING MASTIC SEALANT
- 2 BED ANGLE WITH TRIFLEX CRYL PASTE C.A 1mm
- 3 METAL / GRP FLASHING
- 4 METAL / GRP ANGLE



ROOFS | ROOF DETAILS | REPAIRS

ASPHALT / COATED ASPHALT

CEMENTITIOUS SCREED




GENERAL NOTES

This drawing and any reference to structural / thermal elements should be treated as indicative only and read in conjunction with the Triflex Project specification proposal and relevant Triflex technical data. Details should be verified for accuracy and suitability as we specifically exclude any liability for errors, omissions or otherwise.

The drawing should not be reproduced or amended except with the written permission of Triflex. Do not scale, use figured dimensions only, and check all dimensions on site.

INDICATIVE SYSTEM BUILD-UP



SYSTEM

TRIFLEX PROTECT® WITH
HEAVY DUTY FINISH

PROJECT

STANDARD

DETAIL

PERIMETER VENTED UPSTAND

DRAWING NUMBER

PROTECT_HD_023_PERIMETER
VENTED_UPSTAND

SCALE

NTS

DATE

22/03/2019

REVISION

A

Triflex
Delivering solutions together

Triflex (UK) Limited

Whitebridge Way | Stone | Staffs
ST15 8JS | Tel: 01785 819119
www.triflex.co.uk | info@triflex.co.uk